

Dredging Projects at BAE Systems San Diego Ship Repair

*Maintenance, Capital Improvement, and Cleanup
Dredging*

*Barry Snyder, Kimbrie Gobbi, and Tyler Huff – AMEC E&I
Shaun Halvax – BAE Systems San Diego Ship Repair*



BAE Systems San Diego Ship Repair



- 40-acre facility (composed of 23-acres of land and 17-acres of water) located on Port of San Diego Tidelands
- One of 3 major San Diego shipyards: National Steel & Shipbuilding Company (NASSCO) and Continental Maritime of San Diego
- The site has been in operation as a shipyard since 1915 (prior operators San Diego Marine Construction and Campbell Industries)
- BAE Systems (and its predecessor company Southwest Marine) took over the site in 1979
- Operations include ship repair, modification, and maintenance
- Primary client is the US Navy (facility is of strategic importance)
- Operate a dry dock capable of servicing up to LHD Class Navy Ships

BAE Systems San Diego Ship Repair Location Map



Dredging Projects at BAE Systems San Diego Ship Repair



1. Pride of San Diego (POSD) Dry Dock Sump Dredging
 - Dredging with upland disposal
2. Pier 4 Replacement Project Dredging
 - Pier demolition and replacement
 - Wharf restoration
 - Dredging with ocean and upland disposal
3. San Diego Clean Bay Project Dredging
 - Cleanup and abatement order dredging with upland disposal

Pride of San Diego (POSD) Dry Dock Sump Dredging Project Features



■ Project Description

- Maintenance dredge accumulated sediment from POSD Dry Dock Sump
- Dry dock sump constructed in 1984; operational depth is -70 ft. MLLW; No dredging since 1984
- On-scow thickening with cement; stockpiling; and landfill classification
- Environmental bucket/double silt curtain
- Post-dredge sediment confirmation testing in the CAO Area

■ Disposal Volume and Disposal Location

- Upland disposal at Otay Landfill: ~7,900 cy total; ~2000 cy within the remedial footprint (completed in January 2011)

■ Project Team

- AMEC – Sediment characterization, permitting, and construction/post-construction monitoring
- Anchor QEA – Water quality control plan
- R.E. Staite – Dredging and disposal operations
- Merkel & Associates – Biological monitoring
- BAE Systems – Project design

POSD Dry Dock Sump Dredging Project Location




POSD Dry Dock Sump Dredging


Dry Dock in Operation




POSD Dry Dock Sump Dredging Cross Section




POSD Dry Dock Sump Dredging Dredge Footprint Compared to CAO Area



POSD Dry Dock Sump Dredging Project Implementation Plan



POSD Dry Dock Sump Dredging Dredging Area Showing Silt Curtain Deployment



POSD Dry Dock Sump Dredging Environmental Bucket



POSD Dry Dock Sump Dredging Thickening Agent Injector and Mixer



POSD Dry Dock Sump Dredging Injecting Thickening Agent



POSD Dry Dock Sump Dredging Injecting Thickening Agent



POSD Dry Dock Sump Dredging Transporting Sediment to Stockpile Area



POSD Dry Dock Sump Dredging Dredged Material Dewatering Recovery System



POSD Dry Dock Sump Dredging Dredged Material Dewatering Recovery System



Pier 4 Replacement Project Dredging Project Features



■ Project Description

- Demolition of 2 dilapidated piers and construction of a replacement Pier 4
- Dredging with ocean and upland disposal
- Waste classification and landfill acceptance of in-place sediments
- Early warning (autonomous) system for water quality monitoring per EIR MMRP
- Biological monitoring during dredging and pile driving (eelgrass, birds, marine mammals, turtles)
- Post-dredge sediment confirmation testing in CAO remedial area per RAP requirements


■ Disposal Volumes and Location

- Upland disposal at Otay Landfill: ~19,000 cy total; ~6,000 cy within the remedial footprint (completed in June 2013)
- Ocean disposal at LA-5: ~35,000 cy (dredging in 2014)

■ Project Team

- AMEC – Sediment characterization, permitting, and construction/post-construction monitoring
- R.E. Staite – Demolition, construction, dredging, and disposal
- Tierra Data – Water quality monitoring
- Merkel & Associates – Biological monitoring
- Triton Engineers – Project design

Pier 4 Replacement Project Dredging Project Location




Pier 4 Replacement Project Dredging

Recently Demolished Piers 4 and 5



Pier 4 Replacement Project Dredging Recently Demolished Pier 4

Before Demolition



Alignment of New Pier 4



Pier 4 Replacement Project Dredging Sediment Core Collection



Pier 4 Replacement Project Dredging Sediment Core Collection



Pier 4 Replacement Project Dredging Sediment Core Collection



LEGEND

CAO BAE Remedial Boundary

New Bulkhead

U.S. Pierhead Line

Port District Jurisdiction

State Lands Commission/
California Coastal
Commission Jurisdiction

Demolition Work Area

Pier 4 After Replacement

Project Phase


Phase A1

Phase A2

Phase B1

Phase B2

Phase C



Pier 4 Replacement Project Dredging


Dredge Footprints
Showing Areas
Permitted for Upland
and Ocean Disposal
and CAO Boundary

Pier 4 Replacement Project Dredging Landfill Classification and Approval

- Provided Republic Landfill staff with a waste classification proposal
- Collected 30 push-core samples for analysis of 17 heavy metals, PCBs, and extended range TPH
- Five composites were analyzed for VOCs, SVOC, pesticides, and herbicides
- Waste profile classification and acceptance of in-place sediments
- No sediment stockpile and reanalysis necessary (except paint filter test)




Pier 4 Replacement Dredging Project Dredge Water Quality Monitoring



Compliance Monitoring

Pier 4 Replacement Project Dredging Water Quality Monitoring Stations



Pier 4 Replacement Project Dredging Dredging Operations



Pier 4 Replacement Project Dredging Sediment Thickening with Cement





Pier 4 Replacement Project Dredging Bulkhead Replacement



Pier 4 Replacement Project Dredging Bulkhead Replacement



Pier 4 Replacement Project Dredging Post-Dredge Confirmation Testing



San Diego Clean Bay Project (“The Big Dig”)

Project Features at BAE Systems



■ Project Description

- RWQCB Cleanup and Abatement Order (CAO No. R9-2012-0024)
- Dredging with upland disposal; some wharf and pier improvements
- Waste classification and landfill acceptance of in-place sediments
- Early warning (autonomous) system for water quality monitoring
- Biological (birds, marine mammals, turtles) monitoring during dredging operations
- Sediment confirmation testing to meet post-dredge cleanup goals identified in the CAO
- Post-remedial monitoring – sediment chemistry, toxicity, and bioaccumulation analyses at 2 and 5 years post-remediation; benthic infaunal analyses 3 and 4 years post-remediation


■ Disposal Volumes and Location

- Upland Disposal at Otay Landfill: ~ 105,000 cy (Dredging likely to begin September 2014)

■ Project Team

- AMEC – Sediment characterization and landfill classification
- Anchor QEA – Project planning and design
- Merkel & Associates – Biological monitoring plans and surveys
- Dredging and dredge/post-dredge environmental monitoring – TBD

San Diego Clean Bay Project Sediment Management Units



San Diego Clean Bay Project CAO Dredging/Construction Footprints



Recent Dredging Projects at BAE Systems San Diego Ship Repair - Questions



Acknowledgments:
Michael Whelan – Anchor QEA
Brent Mardian – TDI
Randy Jaeger – BAE Systems
R.E. Staite - Photographs

Thank You WEDA!