


The Restoration of the Cedar Bayou and Vinson Slough Inlet

Thomas Everett, PE





Importance

Red Drum



- Ecology
- TX Economics
 - 15,000+ jobs
 - \$952 million/yr (NMFS, 2011)

Blue Crab




- Primary food source of Whooping Cranes
- Commercial & recreational fishery
- Numbers declining

Whooping Crane



- Critically endangered
- Eat Blue Crabs
- Large eco-tourist industry






Oil from Ixtoc I Oil spill → Matagorda Island in 1979.

Morphology

Open Closed




Cedar Bayou State




- 1929: Unnamed Hurricane
- 1936: Unnamed Hurricane
- 1939: Cedar Bayou Dredging
- 1959: Cedar Bayou Dredging
- 1961: Hurricane Carla
- 1970: Hurricane Celia
- 1971: Tropical Storm Fran
- 1979: Emergency Closure due to Ixtoc I Oil Spill
- 1987: Cedar Bayou Dredging
- 1995: Cedar Bayou Dredging
- 2003: Hurricane Claudette
- 2007: Tropical Depression Erin
- 2014: Cedar Bayou/Vinson Slough Restoration Project
- 2017: Hurricane Harvey
- 2021: Cedar Bayou/Vinson Slough Restoration Project



1971



1984



1987





Pre-Construction, July 2014




Post-Construction, November 2014

Hurricane Harvey impacts on Habitat






Habitat Timeline 2014 - 2022




Adaptive Management Approach

- Cross section matches the previous design.
- Template adjusted to minimize dredge volume and avoid sensitive habitats.
- Will achieve a more natural channel, matching historical channel alignments.
- Maximize flow through Cedar Bayou and Vinson Slough.
- Maintenance Permit to allow for adjustment of the template within the Cedar Bayou Migration Zone.



Data Collection


Aerial Photograph – Oct 2020




Data Collection

Historical Thalwegs


- Channel thalwegs dating back to 1969
- Natural flow paths and trends are used to help guide the design



Previous and Proposed Template



PREVIOUS
2014




PROPOSED
2021

LEGEND


- +--- CONTOUR (NAVD88)
- - - MHHW +0.5'
- - - DREDGE BOTTOM OF CHANNEL CL
- - - SILT FENCE
- - - WORK AREA LIMITS
- ▨ PLACEMENT AREA
- ▨ DREDGE LIMITS
- ▨ CONTRACTOR STAGING AREA
- ▨ TRUCK HAUL ROUTE AND PIPELINE CORRIDOR
- ↖ PROJECT SIGN

NOTES


1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE TRANSPORTED TO AND FROM THE PROJECT SITE VIA THE GULF OF MEXICO OR THE MESQUITE BAY ACCESS ROUTE ONLY.
2. CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE STAGED AND/OR STORED WITHIN THE CONTRACTOR STAGING AREA ONLY.
3. DREDGED AND EXCAVATED MATERIAL SHALL BE PLACED WITHIN DESIGNATED PLACEMENT AREA.
4. WORK AREA LIMITS ARE 15' OUTSIDE TOP OF DREDGE SLOPE AND 2' OUTSIDE OF THE TRUCK HAUL ROUTE AND PIPELINE CORRIDOR.
5. SIGN LOCATION SHOWN IS APPROXIMATE. FINAL INSTALLED LOCATION WILL BE DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE OWNER.
6. SILT FENCE LOCATIONS ARE APPROXIMATE. FENCE LOCATIONS SHALL BE DETERMINED BASED ON PRE-CONSTRUCTION HABITAT SURVEY AND BE MODIFIED THROUGHOUT CONSTRUCTION AS NEEDED.



OVERALL SITE PLAN



TYPICAL SECTION
VINSON SLOUGH



TYPICAL SECTION
CEDAR BAYOU



100% DESIGN

Bidding and Construction


Timeline

Activity	Target Date
100% Design Submittal	11/16/2020
Bid Advertisement	11/28/2020
Bid Opening	12/28/2020
Construction Contract Award	12/29/2020
Pre-Construction Conference	03/04/2021
Notice to Proceed	03/04/2021
<u>Mobilization to Site</u>	<u>04/30/2021</u>
<u>Start of Dredging</u>	<u>06/05/2021</u>
Demobilization	12/01/2021



Supply Chain Issues in the Industry

- Ongoing supply chain issues resulting from COVID-19
- Sourcing equipment and scheduling surveyors/other personnel
- Important to take into consideration when planning construction schedule



Equipment

Mechanical Dredging Operations

- 2 x Excavators and 8 - 10 x trucks on average

Hydraulic Dredging Operations

- 2 x hydraulic dredges 14" and 12" cutterhead
- 4 booster pump stations. 2 for each line


Other Equipment

- Marsh buggy, fuel buggies, equipment barges, and bulldozers






Pipeline transporting dredged material from cutter head dredges to disposal area.



Contractor boosting production through mechanical excavation, digging ahead of hydraulic dredges, and transporting material via off-road trucks.





Cutter suction dredge deepening the Cedar Bayou Dredge template.



Inlet opening after hydraulic connection to the Gulf of Mexico prematurely re-established by the passing of Hurricane Nicholas.

Channel Migration Comparison

2015 (after opening)




- Historical Migration rate = ~266 ft/yr
- Migration typically stabilizes over time


2022 (after opening)



2021 Construction Summary

1. Cedar Bayou and part of Vinson Slough were dredged. Vinson Slough had a partial hydraulic connection
2. The mouth of Cedar Bayou was open to the Gulf of Mexico
3. Due to construction delays and tight environmental window, the full design template in Vinson Slough was unfinished
4. To ensure the longevity of the system, the decision was made to finish Vinson Slough template in 2022







2022 Dredge Operations

- Bell 250 pump with Suction Head mounted on a CAT swamp buggy
- 12" pipeline from pump runs to placement area
- Equipment setup rated for ~2000 yd/day



Summary

- Adaptive management approach has worked well for Cedar Bayou. We have observed a stable channel after opening which contributes to the longevity of the project.
- Challenges from COVID-19 caused contractor to not finish on time in 2021
- However, the delay allows us to continue to make minor improvements to the template alignment
- Once the remaining portion of the Vinson Slough template is dredged, a complete hydraulic connection will be established throughout the system.
- Monitoring will continue 2 years post construction completion (2024)



Questions?

Thomas Everett, P.E.

Thomas.Everett@mottmac.com
512-777-3066

