


NAD/SAD/SWD/MRD Regional Dredging Meeting/WEDA


Savannah District



US Army Corps of Engineers
BUILDING STRONG®



Civil Works & Navigation Boundaries



Navigation Projects



◆ Sav'h Harbor	32.5 Miles
◆ AIWW	161 Miles
◆ Brunswick	24 Miles

Total	217.5 Miles
--------------	--------------------



Scheduled FY13 Dredging Work in Savannah District

South Atlantic Division

		OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
Hopper Dredge Maintenance Dredging													
Savannah & Brunswick Entrance Channels	BO 30				Sea Turtles-screens & observers								
					Est. 1,000 K CY								
Hydraulic Pipeline Dredge Maintenance Dredging													
Savannah & Brunswick Inner Harbors	BO 25						Striped bass spawning				DO Window		
							Est. 6,000K CY						



Savannah District

FY 13 Hopper Dredge Program



Scheduled FY13 Dredging Work in Savannah

District


South Atlantic Division

Hopper Dredge
Maintenance Dredging

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
Savannah & Brunswick Entrance Channel	BO 30			Sea Turtles-screens & observers								
				Est. 1,000K CY								




Savannah District



- Project: Savannah Entrance Channel
- Type of work: Maintenance
- Depth: 42/44 ft
- Width: 600 ft
- Length: 11.4 miles
- Quantity: 600 KCY
- Type of Material: sand/silt/clay
- Placement Areas: EPA approved ocean site
- Distance to Placement Area: up to 11.5 miles
- Type of Equipment: Hopper
- Small Business Set Aside: No
- Last Dredged: FY12
- Environmental Window: Dec 15- March 31
- Reason for Window: Right Whales and Sea Turtles



Savannah District



- Project: Brunswick Entrance Channel
- Type Work: Maintenance
- Depth: 36/38 feet
- Width: 500 feet
- Length: 16.8 miles
- Quantity: 400 KCY
- Type of Material: Sand/silt/clay
- Placement Areas: EPA approved ocean site
- Distance to Placement Area: up to 19 miles
- Type of Equipment: Hopper
- Small Business Set Aside: No
- Last Dredged: FY12
- Environmental Window: Jan 1- Feb 28
- Reason for Window: Right Whales and Sea Turtles



Savannah District

FY13 Hydraulic Cutter Head Dredge Program



Scheduled FY13 Dredging Work in Savannah District



South Atlantic Division

OCT NOV DEC JAN FEB MAR APR MAY JUN JUL AUG SEP

Hydraulic Pipeline Dredge Maintenance Dredging												
Savannah & Brunswick Inner Harbor	BO 25					Striped bass spawning			DO Window			
						Est. 6,000K CY						



Savannah District



- Project: Savannah & Brunswick Inner Harbors
- Type of work: Maintenance
- Depth: (SH)40/46 ft, (BH)36 ft
- Width: (SH)500 ft, (BH)400 ft
- Length: (SH)21.3 miles, (BH)3 miles
- Quantity: 6.0 mcy
- Type of Material: sand/silt/mud
- Placement Area: Upland placement sites
- Distance to Placement Area: up to 2 miles
- Type of Equipment: Hydraulic cutterhead pipeline
- Small Business Set Aside: No
- Last Dredged: FY12
- Environmental Window: (SH) March 15-May 30 & July 1-September 30 (above Station 63+000) (BH) April 1-August 1
- Reason for Window: (SH) Striped Bass Spawning & Low DO (BH) Least tern nesting

