

Raccoon Island Marsh Creation Project Terribonne Parish Louisiana

Client: Weeks Marine – general contractor

State of Louisiana USDA - Natural

Resources Conservation Service (NRCS)

Project Location: located on the westernmost island within

the Deernieres Barrier Island Refuge approximately 25 miles southwest of

Cocodrie, La in the Gulf of Mexico.

Objective: This barrier island shoreline protection and

marsh creation project was initiated to

protect against tropical storms and provide

additional space for the rookery an

important nesting colony for the brown

pelican and other species of colonial

wading sea birds.

Overview: Build an approximately 58 acre containment area filled

to elevation +3.0, berm heights maintained at elevation

+4.0. An approximately 640,000 cubic yards of fill

from an adjacent borrow area was used to place the fill

in the containment area using a hydraulic dredge.

IAI Scope: To reconstruct and maintain the berm

impacted by erosion, followed by installing geotextile tube wave and tide energy breaks along the length of the berm to prevent further

damage.

Time Period: March – April 2013

Crew Size: 8 to 12

Equipment: (4) Marsh buggy excavators

(2) Deck barges, 80' & 120' long


Quarters barge with 18 ton deck crane

75 HP 8" electric submersible pump & jet ring

6" dry prime pump

200 kW generator









Phase 1



Installation of 400' of 30' circumference geotextile tubes, deployed and filled on top of 25' scour aprons with anchor tube on the sea side.

03/18/2013 19:26









Ramp barge used to store geotextile tubes and scour aprons and as a working platform.

03/18/2013 19:24

















Problems/Issues To Overcome









Extremely fine sand and clay












Phase 2



Installation of 4,620' of 50' wide scour apron over the reformed berm. Prior to placement of the apron the newly shaped berm was covered with 6 mil Visqueen. The apron was deployed and an anchor tube along each side was hydraulically filled to prevent the apron from being undermined by tide or surf.

04/21/2013 12:02



















After IAI had completed our portion of the project additional project scope required planting vegetation which was performed by others however the berms continued to hold up well with this system.







INFRASTRUCTURE ALTERNATIVES



The End



INFRASTRUCTURE ALTERNATIVES