CH2MHILL.

Waukegan Harbor - Dredging Towards Revitalization





Western Dredging Association (WEDA)
Midwest Chapter Annual Meeting – April 2013



George L. Hicks – CH2M HILL

Overview

- Project Background
- Design
- Remediation
- Current Status of the Project
- Waukegan Harbor The Vision



Site Description

- Located on western shore of Lake Michigan in Waukegan, Illinois
- Approximately 40 acres
- Man-made harbor w/ no tributary flows
- Currently used by industrial and recreational vessels
- Federal navigation channel, with authorized depth of -18 feet LWD (Not dredged since early 1970s because of PCBs)




Site Background

- OMC manufactured marine products from about 1948 until Dec 2000
- Used hydraulic fluids, cutting oils, and die cast oils with PCBs until about 1972
 Estimated ~ 300,000 pounds of PCBs released to Waukegan Harbor
- Operated solvent vapor degreasers
 TCE DNAPL and dissolved phase contamination
- USEPA issued ROD in 1984

CH2MHIL

NORTH SHORE SANITARY DISTRICT





Site Background (continued)

- OMC conducted RA in 1990-1992 to clean up harbor and facility grounds
- Discovered creosote during construction of Slip 4 – WCP (OU 2)
 RA currently being conducted by PRP Group
- OMC declared bankruptcy in 2000
- City of Waukegan purchased
 Waukegan Coke Plant (2002) and
 OMC Plant 2 properties (2005)

Company Confidential CH2MHII





Site Background (continued)

- CH2M HILL Involved since 2004
- Completed RI/FS in 2008
- Record of Decision in October 2009
- Initiated design for USEPA's Superfund Division in 2009
- Submitted final design in March 2011
- Received RA work assignment in June 2011
- Dredging Began 2012

Company Confidential CH2MHIL



Waukegan Harbor Remedial Design

ROD Amendment Option

- Construction of containment facility on OMC Plant 2 property
- Hydraulic dredging of impacted sediments
- Sediment dewatering using geotextile tubes on OMC Plant 2 site
- Treatment and discharge of water back into harbor
- Demolition of piers in North Marina
- Estimated Cost: ~\$42M

CH2MHIL

Waukegan Harbor Site



Waukegan Harbor Site



Waukegan Harbor Site






Waukegan Harbor Contractors

Activity	Contractor
Site Construction	J.J. Henderson
Dredging	J.F. Brennan
Sediment Processing Systems Operations	Infrastructure Alternatives Inc
North Marina Demolition	J.F Brennan
Seawall Reconstruction	Rausch Construction company, Inc.\$ 1M

CH2MHILL.

Dredge Management Units











Current Status of Project

Total Pre-Dredge Volume to Design:125,808 cy

- Surveyed 6,284 cy/wk (Total to Date = 54,351 cy)
- Volume remaining = 71,457 cy


Milestones	Estimated Schedule (Jan 2013)
Dredge/Ops Start (Season 2)	April 2013
North Marina Demolition Complete	June 2013
Dredging Complete	July 2013
Processing Complete (Season 2)	August 2013
In-water Work complete	December 2013
System Demobilization Complete	July 16, 2014

Waukegan Harbor – The Vision

- Downtown Waukegan to return to its roots as a vibrant city center, a place for jobs, shopping, entertainment and urban living
- The South Lakefront and the Harborfront to become home to new waterfront neighborhoods.
- The North Lakefront to become an international model for environmental and ecological restoration.



Waukegan Harbor – The Vision



Questions?

