

Esquimalt Graving Dock Waterlot Phase 2 South Jetty Remediation Design and Construction Challenges



Matt Woltman, P.E., L.E.G., Anchor QEA, LLC

Site Location



Multiphase Project Description and Objectives



Multiphase Project Description and Objectives

- Phase 2: Jetty demolition and under-pier remediation
 - 36,150 m³ contaminated sediment removal
 - Required Dredging (with payable overdredge): 34,400 m³
 - Missed inventory (contingency): 1,750 m³
 - Hazardous waste removal volume: 200 m³
 - 38,700 m³ engineered capping material placement
 - Sand material: 24,750 m³
 - Filter material: 6,050 m³
 - Armour material: 7,900 m³
 - Remediation activities performed in open-water and under-pier areas

Multiphase Project Description and Objectives

- Other activities
 - Timber jetty demolition and asphalt removal
 - Steel sheet pile wall re-drive
 - Temporary re-suspension barrier (TRB) installation and maintenance
 - Utility upgrades
 - Cathodic protection system re-installation
- Construction from October 2015 to December 2016
 - Remove maximum contamination practicable
 - Prepare site for jetty reconstruction
 - Project in tender now; construction to start late 2017

- South Jetty demolition and asphalt removal/disposal
- Temporary re-suspension barrier
- Dredging access/material removal
- Residuals generation/management
- Engineered sediment cap construction





South Jetty demolition and asphalt removal/disposal




- Timber jetty to be demolished
- Steel pile-supported jetty to be retained

South Jetty demolition and asphalt removal/disposal













Temporary re-suspension barrier




Temporary re-suspension barrier







Dredging access/material removal




Dredging access/material removal








Dredging access/material removal





Residuals generation/management




Residuals generation/management









Engineered sediment cap construction



Engineered sediment cap construction







Engineered sediment cap construction







Lessons Learned

- Assess/evaluate contingency approach during design and project tender
- Evaluate project schedule with conservative production rates and contingency allowances
- Conduct thorough cash flow forecasting and quantity balancing on routine (i.e., monthly) basis
- Work adaptively with contractor
 - Maintain design intent
 - Achieve remediation objectives



Questions

 Matt Woltman, P.E., L.E.G., <u>mwoltman@anchorgea.com</u>